



EQUIPMENT SCHEDULE						
ItemNo	Category	Mfr	Model	Quantity	Equipment Remarks	
151	Dishwasher, Door Type	Hobart	AM16-ASR-2	1	Existing	
152	Clean Dishtable	Advance Tabco	DTC-S70-84R	1	Existing	
153	Dishable, Soiled "L" Shaped	Advance Tabco	DTS-D70-108L	1	Existing	
155	Three (3) Compartment Sink	Advance Tabco	FC-3-2424-24RL	1		
155.1	Wall / Splash Mount Faucet	Krowne	14-814L	2		
156	Overshelf	Advance Tabco	PS-15-48	2		
214	Gas Floor Fryer	Jade (Middleby)	JTFE-40-18	2		
215	HD Range, 18", French Hot Top	Jade (Middleby)	JMRH-1FHT	4		
216	Equipment Stand, Refrigerated Base	Continental Refrigerator	D60GN	2		
217	HD Range, 30" Plancha	Jade (Middleby)	JMRH-30IP	1		
218	HD Range, 30" Charbroiler	Jade (Middleby)	JMRH-30B	1		
219	Combi Oven, Gas	RATIONAL	ICP 10-HALF LP 120V 1 PH (LM100DG)	2		
		RATIONAL	8720.1560US	2		
220	Salamander Broiler, Electric	Hatco	SAL-1-208	1		
222	Custom Cooking Suite	Custom Fab	SUITE	1		
222.1	Hot Food Well Unit, Drop-In, Electric	Wells (Middleby)	MOD-100TD	2		
222.2	Dipper Well	Krowne	16-149	2		
226	Counter Enclosed	Custom Fab	TABLE	1		
226.1	Dipper Well	Krowne	16-149	1		
226.2	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		
227	Undercounter Refrigerator	Continental Refrigerator	UC48SN	1		
231	Counter	Custom Fab	TABLE GM	1		
231.1	Deck Mount Faucet	Krowne	15-410L	1		
231.2	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		
231.3	Overshelf	Advance Tabco	DCM-18-72	1		
232	Undercounter Refrigerator	Continental Refrigerator	UC48SN	2		
234	Table	Custom Fab	TABLE L	1		
234.1	Dipper Well	Krowne	16-149	1		
234.2	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		
235	Undercounter Refrigerator	Continental Refrigerator	UC24SN	1		
236	Refrigerated Work Top	Continental Refrigerator	RA43SNBS-D	1		
236.1	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		
238	Table	Custom Fab	TABLE L	1		
238.1	Dipper Well	Krowne	16-149	1		
238.2	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		
239	Undercounter Refrigerator	Continental Refrigerator	UC48SN	2		
242	Table	Custom Fab	TABLE	1		
242.1	Cabinet, Wall-Mounted	Custom Fab	CABINET	1		

# EQUIPMENT LAYOUT

All Dimensions to be verified on the job site.  
 Actual locations for floor drains, and any ventilating equipment to be determined by Engineer.  
 Mechanical, Plumbing & Electrical to be checked and verified by Customers MEP Engineer.  
 Remote Condensing Units to be located by Architect.  
 Exhaust & Supply fans to be located by Architect.

Lyford Cay  
 Little Club  
 Nassau, Bahamas



INTERNATIONAL INC.

2055 W 73rd Street, Miami, FL 33016  
 Ph: (305)826-8696 Fax: (305)826-9131

1	Preliminary Layout	1-24-25
2		
3		
4		
No.	Revision/Issue	Date

Date  
**Jan 24, 2025**  
 Drawn By  
**Dayne Gauntlett**  
 Scale  
**3/8" = 1'0"**

Sheet  
**FS-1.0**